

Gaylord Street



NOTES

1. THE RECORD OWNER OF THE SUBJECT PARCEL IS FUEL SERVICES, INC. SEE HAMPSHIRE COUNTY REGISTRY OF DEEDS LAND COURT CERTIFICATE #2485.
2. THE PROPERTY LINES SHOWN HEREON ARE BASED UPON AN UNRECORDED LAND COURT SUBDIVISION PLAN TITLED, "LAND COURT SUBDIVISION - PLAN OF LAND IN THE TOWN OF SOUTH HADLEY, MASSACHUSETTS - HAMPSHIRE COUNTY - PREPARED FOR FUEL SERVICES, INC." PREPARED BY DURKEE, WHITE, TOWNE AND CHAPDELAIN, DATED 01/23/2016; REVISED TO 02/01/2017.
3. THE EXISTING BUILDING(S) SHOWN HEREON ARE BASED ON AN APPROXIMATE MEASUREMENT OF THE OUTSIDE PERIMETER OF THE EXISTING STRUCTURES. THE ACTUAL LOCATION OF THE EXISTING BUILDING WALLS AND CORNERS SHOULD BE VERIFIED IN THE FIELD PRIOR TO ANY CONSTRUCTION WORK THAT WOULD ABUT OR TAKE PLACE ADJACENT TO THE EXISTING BUILDING(S). IF THE PLAN HEREON IS USED FOR CONSTRUCTION LAYOUT PURPOSES, THE PARTIES CONDUCTING LAYOUT SHALL CONTACT R. LEVESQUE ASSOCIATES INC. PRIOR TO SAID LAYOUT TO DETERMINE PROPER CONTROL. PLEASE NOTE WHILE THE BUILDING(S) ARE SHOWN TO BE SQUARE, IT SHOULD NOT BE ASSUMED THAT THE WALLS ARE SQUARE OR PLUMB. R. LEVESQUE ASSOCIATES TAKES NO RESPONSIBILITY FOR THIRD PARTY LAYOUT OF THE PLAN SHOWN HEREON.
4. THIS PLAN HAS BEEN PREPARED FOR SITE PLANNING PURPOSES AND SHALL NOT BE USED FOR THE CONVEYANCE OF LAND OR FOR ANY OTHER USE.
5. SUBJECT PARCEL CONTAINS 83,305 S.F.
6. THE SUBJECT PROPERTIES SHOWN HEREON MAY BE SUBJECT TO RIGHTS AND EASEMENTS AS CONTAINED IN THE VARIOUS DEEDS OF RECORD DESCRIBING SAID PROPERTIES. THE LOCATION AND EXTENT OF ANY SUCH RIGHTS AND EASEMENTS IS NOT THE SUBJECT OF THIS PLAN.
7. THE MEAN ANNUAL HIGH WATER LINE WAS DELINEATED BY R. LEVESQUE ASSOCIATES, INC. PERSONNEL ON 09-17-2020 AND LOCATED BY TRANSIT SURVEY.
8. THE EXISTING CONDITIONS INFORMATION SHOWN IS BASED UPON A TOPOGRAPHIC SURVEY PERFORMED BY R. LEVESQUE ASSOCIATES, INC. ON SEPTEMBER 17, 2020.
9. THE UNDERGROUND UTILITIES SHOWN HEREON HAVE BEEN LOCATED FROM FIELD SURVEY INFORMATION, DIGSAFE MARKINGS AND AVAILABLE RECORD DATA. R. LEVESQUE ASSOCIATES, INC. MAKES NO GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN HEREON COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. R. LEVESQUE ASSOCIATES, INC. FURTHER DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN HERE ARE IN THE EXACT LOCATION INDICATED, ALTHOUGH THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM AVAILABLE INFORMATION.
10. ADJACENT PROPERTY LINES AND ABUTTERS SHOWN HEREON ARE REFERENCED FROM THE TOWN OF SOUTH HADLEY MUNICIPAL GIS WEBSITE.
11. SUBJECT PARCEL IS ZONED INDUSTRIAL B ACCORDING TO THE TOWN OF SOUTH HADLEY ZONING MAP.
12. A PORTION OF THE SUBJECT PARCEL IS LOCATED WITHIN SPECIAL FLOOD ZONE AREA AE ACCORDING TO FLOOD INSURANCE RATE MAP NUMBER 2501700010A - EFFECTIVE DATE: AUGUST 15, 1979. 100 YEAR FLOOD ELEVATION = 73.30 (CONVERTED FROM NGVD 29 DATUM TO NAVD 88 DATUM).
13. THE SUBJECT PROPERTY IS NOT LOCATED WITHIN NATURAL HERITAGE & ENDANGERED SPECIES PROGRAM (NHESP) JURISDICTION.

Gaylord Street

ZONING REVIEW - Industrial B (IB)		
TYPE (MINIMUM)	REQUIRED	PROPOSED
AREA	NONE	83,305 S.F.
FRONTAGE	NONE	499.82
MAX. LOT COVERAGE (PRINCIPAL USES)*	75%	23.7%
MAX. LOT COVER. (ACCESS. USES) - EXIST.G.*	20%	0.7%
MAX. LOT COVER. (ACCESS. USES) - PROP.*	20%	4.3%
FRONT YARD	NONE	42±
SIDE YARD	NONE	12±
REAR YARD	NONE	4±
MAX. HEIGHT (PRINCIPAL USES)	6 STORIES/75 FT.	1 STORY/<75 FT.
MAX. HEIGHT (ACCESSORY USES)	6 STORIES/75 FT.	1 STORY/26±

* TOTAL LOT COVERAGE OF PRINCIPAL AND ACCESSORY USES SHALL NOT EXCEED THE MAXIMUM PERMITTED FOR PRINCIPAL USE




STANDARD RIP RAP PIPE OUTLET
NO SCALE

PERMITTING

NOTICE OF INTENT FILING PLAN

27 Gaylord Street
Assessors parcel 018-0110-000
South Hadley, Mass.



PREPARED FOR:
FSI Oil and Propane, Inc.
c/o Mr. William Zych
V.P. Transportation and Safety
95 Main Street
South Hadley, MA 01075



ISSUANCE DATE:	DATE:
November 16, 2020	
A. Culvert Outlet Repair Notes	12/9/2020
B. Oil Water Separator Added	12/31/2020
C. Amended Order of Conditions	07/28/2021

DRAFTED BY: J.W.M.
UNAUTHORIZED ALTERATION OF THIS DOCUMENT IS A VIOLATION OF MASSACHUSETTS STATE LAW


SCALE: 1" = 20'

RLA PROJ. NUMBER: 200811

DRAWING# REV.
W-1 C



S:\Projects\2020\200811 - Zych - 28 Gaylord St., South Hadley\Civil\3D\200811 - SITE -REVB - 2021-07-27.dwg



Anne Capra <acapra@southhadleyma.gov>

Revised Site Plan

1 message

Bill Zych <BZych@fuelservices.biz>

Thu, Aug 5, 2021 at 8:31 AM

To: "acapra@southhadleyma.gov" <acapra@southhadleyma.gov>

Hello,

We have revised the site plan for the new building on Gaylord St. I have attached the plans and are requesting an amendment to the Order of Conditions. We have shifted the building slightly. You will also notice the OWS location has changed and the size and design are included based on plans from WEB Engineering. I can provide the OWS plans if needed.

Please let us know if there is anything else we can provide.

Thank You

Bill Zych

*William Zych**V.P. Transportation and Safety*

FSi Oil and Propane, Inc.

95 Main St

South Hadley, MA 01075

WWW.FUELSERVICES.BIZ

Phone 413-532-3500

Fax 413-532-0052

**GAYLORD2021-07-28 - REVISED NOI FILING PLAN RL Stamp.pdf**

546K